



Notes:

1. Compound layout and elevations refer to both Compound 1 (North) & Compound 2 (South).
2. Size, number and location of compound equipment & facilities are indicative only.
3. Structure to be temporary and to be removed after construction.
4. Compound hardstanding consisting of compacted stone over a layer of geotextile to provide a clean, firm, level and free draining surface suitable for cabins and heavy traffic.
5. Vehicular access gate to be 6m wide consisting of 2x3m leaves.

Drawn By: Jamie McGhee  
 Address: Wright Business Centre  
 1 Lonmay Road  
 Glasgow  
 G33 4EL

Ver.	Date	Comments
A	22/01/2021	



Warrington Office: T:01925 661716 E: info@neo-environmental.co.uk  
 Glasgow Office: T: 0141 773 6262 E: info@neo-environmental.co.uk  
 Naas Office: T:00353 (0)45 844250 E: info@neo-environmental.ie  
 Ballymena Office: T:0282 565 0413 E: info@neo-environmental.co.uk

<b>Project:</b>	Derril Water Solar Farm
<b>Client:</b>	RES
<b>Drawing:</b>	Construction Compound Detail
<b>Project No.:</b>	NEO00738
<b>Drawing No.:</b>	NEO00738_0391_A Figure 7
<b>Drawn:</b> JM	<b>Checked:</b> MM <b>Approved:</b> PN
<b>Scale:</b>	1:250 @ A3 <b>Revision:</b> A
<b>Date:</b>	22 January 2021